
2015 STREETS DRAINAGE & UTILITY PROJECT CITY OF WAYCROSS, GEORGIA

MARCH 27, 2015



CITY OF WAYCROSS

417 PENDLETON STREET WAYCROSS, GEORGIA 31502 (912) 287-2900

MAYOR


CLARENCE E. BILLUPS


COMMISSION

NORMAN E. DAVIS, SR. - DISTRICT I LARRY ETHRIDGE - DISTRICT II MARIAN C. SOLOMON-GAINES - DISTRICT III DIANE L. HOPKINS - DISTRICT IV ALVIN D. NELSON - DISTRICT V

ENGINEERING DIVISION

JESSICA KING DEAL, P.E. - City Engineer GENE THOMAS - Engineering Superintendent





CALL BEFORE YOU DIG!

At least 72 hours prior to commencement of the work, the Contractor is responsible for calling the Utilities Protection Center (UPC) at 1-800-282-7411, to request underground utility locate service.

DATE	ACTION					
MARCH 27, 2015	RELEASED FOR CLIENT AND EPD PLAN REVIEW (NOT FOR CONSTRUCTION)					
				2015		
			7-7	×	;	≥
		.: ON	-00	7 K		SHOWN
			2015-	DATE: MARCH	т ш	AS S
		FILE	••	\ <u>\</u>	SC	
	IS AN INSTRUMENT OF SERVICE AND REMAINS THE COASTAL ENGINEERING CONSULTANTS, INC. THIS	SH	EET	NO.:		
DRAWING MAY	NOT BE REPRODUCED IN WHOLE OR IN PART WITHOUT			Т-	.1	
INC.	PERMISSION OF COASTAL ENGINEERING CONSULTANTS,	ΛE		1	1	

FNAME

REVDATE

JSER

GENERAL NOTES:

EXISTING CONDITIONS SHOWN ON THESE PLANS WERE COMPILED FROM DRAWINGS AND OTHER INFORMATION FURNISHED BY THE CITY OF WAYCROSS AND FROM FIELD SURVEY DATA. SUCH INFORMATION IS BELIEVED TO ACCURATE, HOWEVER PIPE ROUTING MAY BE SCHEMATIC IN SOME AREAS AND SHALL BE VERIFIED BY THE CONTRACTOR IN CRITICAL AREAS SUCH AS CONNECTIONS BETWEEN EXISTING AND PROPOSED UTILITIES.

FIELD SURVEY INFORMATION TAKEN FROM TOPOGRAPHIC AND UTILITY
SURVEY OF IZLAR, OWENS, WALKER AND ROOSEVELT STREETS PREPARED
BY CHARLES H. TOMBERLIN AND ASSOCIATES AND DATED MAY 14, 2012.

THE LOCATION OF EXISTING UTILITIES IS APPROXIMATE AND MAY NOT BE COMPLETE. NO WARRANTY IS MADE, EXPRESSED OR IMPLIED, THAT ACTUAL LOCATIONS WILL NOT VARY FROM THOSE SHOWN. CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND AND OVERHEAD UTILITIES PRIOR TO CONSTRUCTION AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF SAME. CONTRACTOR SHALL NOTIFY THE UTILITIES PROTECTION CENTER (UPC) AT 1-800-282-7411 AT LEAST 72 HOURS IN ADVANCE OF ANY TRENCHING OR EXCAVATION.

SHOULD ACTUAL FIELD CONDITIONS VARY FROM THOSE SHOWN ON THESE PLANS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY AND BEFORE PROCEEDING WITH OR CONTINUING WITH CONSTRUCTION.

CONTRACTOR SHALL MAINTAIN ACCES TO PRIVATE PROPERTY AT ALL TIMES. SUBMIT TRAFFIC CONTROL PLAN FOR APPROVAL PRIOR TO COMMENCING CONSTRUCTION.

IN THE EVENT OF A DISCREPANCY BETWEEN THESE CONSTRUCTION PLANS AND THE PROJECT TECHNICAL SPECIFICATIONS, THE TECHNICAL SPECIFICATIONS SHALL TAKE PRECEDENCE.

ALL DISTURBED AREAS SHALL BE RE-VEGETATED IMMEDIATELY AFTER CONSTRUCTION IN A MANNER CONSISTENT WITH THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA. ALL EROSION AND SEDIMENT CONTROLS SHALL BE INSTALLED PRIOR TO OR CONCURRENT WITH THE START OF CONSTRUCTION.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION LAYOUT AND STAKING INCLUDING SETTING OF GRADES, LINES AND LEVELS; AND THE LOCATION OF EXISTING OR PROPOSED EASEMENTS AND/OR RIGHTS—OF—WAY. THE CONTRACTOR'S SURVEYOR SHALL PROVIDE CENTERLINE ALIGNMENT FOR CONSTRUCTION PURPOSES AND ESTABLISH AND MAINTAIN BENCHMARKS AND HORIZONTAL CONTROL POINTS. THE CONTRACTOR SHALL ASSUME ALL RESPONSIBILITY FOR THE CORRECTNESS OF THE GRADE AND ALIGNMENT STAKES.

THE CONTRACTOR SHALL ALSO ENGAGE THE SERVICES OF A REGISTERED LAND SURVEYOR TO PREPARE AND SUBMIT RECORD DRAWINGS OF THE COMPLETED WATER, SANITARY SEWER, AND STORM DRAINAGE INFRASTRUCTURE.

DEMOLITION NOTES:

FIELD VERIFY EXISTING CONDITIONS WHERE THEY AFFECT DEMOLITION AND NEW CONSTRUCTION TO DETERMINE EXACT LOCATION, ROUTING AND ELEVATIONS OF EXISTING PIPES WHICH ARE SCHEDULED FOR DEMOLITION. CONFIRM FUNCTION AND STATUS OF EACH PIPE (WHETHER ACTIVELY IN SERVICE OR NOT) PRIOR TO DISCONNECTION OR INTERRUPTING SERVICE FOR DEMOLITION. COORDINATE ALL DEMOLITION ACTIVITIES THAT MAY AFFECT WATER AND SEWER SERVICE OR ACCESS TO PRIVATE PROPERTIES WITH THE OWNER. CONTACT JESSICA KING DEAL AT (912) 506-0150 AT LEAST 48 HOURS IN ADVANCE OF ANY DEMOLITION AND UTILITY RELOCATION WORK.

CAP OR PLUG PIPING WHERE ABANDONED IN PLACE USING APPROVED MATERIALS AND METHODS AS DELINEATED IN THE PROJECT SPECIFICATIONS.

AREAS SHOWN FOR COMPLETE PAVEMENT RESTORATION REQUIRE THE COMPLETE REMOVAL OF EXISTING ASPHALT AND BASE MATERIAL. SUBGRADE TO BE REMOVED AS NECESSARY AND REPLACED WITH SUITABLE MATERIALS. PROVIDE 6" OF COMPACTED STONE BASE. SEE SPECIFICATIONS FOR ADDITIONAL DETAILS.

WHERE EXISTING CONCRETE SIDEWALKS AND DRIVEWAYS ARE SHOWN TO BE REMOVED, NEATLY SAW CUT EXISTING PAVEMENTS TO CLEAN STRAIGHT LINES TO THE LIMITS SHOWN OR AS REQUIRED TO ACCOMMODATE NEW CONSTRUCTION.

LIMITS SHOWN ON THE DRAWINGS FOR EXISTING CONCRETE AND SIDEWALK REMOVAL, AS WELL AS AREAS SHOWN FOR COMPLETE PAVEMENT RESTORATION, ARE APPROXIMATE AND MAY NOT BE ALL INCLUSIVE. AREAS NOT SHOWN BUT REQUIRING REMOVAL AT THE DIRECTION OF THE ENGINEER SHALL BE ACCOMPLISHED BY THE CONTRACTOR AT THE UNIT PRICES STATED IN THE BID FORM.

EXISTING ASPHALT SHALL BE MILLED TO AN AVERAGE DEPTH OF 1.5 INCHES OR TO THE DEPTHS SHOWN ON THE EXISTING STREET PROFILES (PLAN SHEETS X-4 AND X-5).

EXISTING SANITARY SEWER MANHOLES SHOWN TO BE ABANDONED SHALL BE REMOVED AS NECESSARY TO ACCOMMODATE NEW CONSTRUCTION. IN GENERAL SUCH STRUCTURES TO REMAIN SHALL BE REMOVED TO A DEPTH AT LEAST THREE (3) FEET BELOW EXISTING GRADE. PUNCH HOLES IN MANHOLE BOTTOMS AND FILL STRUCTURES WITH SAND OR OTHER SUITABLE MATERIALS. SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION.

MATERIALS REMOVED DURING THE DEMOLITION OPERATIONS SHALL BE DISPOSED OF OFFSITE BY THE CONTRACTOR. DISPOSAL SITE SHALL BE AN APPROVED LANDFILL OR OTHER APPROVED RECYCLING OR WASTE DISPOSAL AREA.

ANY REFERENCE POINTS, RIGHT-OF-WAY MONUMENTS, BENCHMARKS OR OTHER MONUMENTS DISTURBED BY CONSTRUCTION OPERATIONS SHALL BE RESTORED BY A REGISTERED LAND SURVEYOR LICENSED TO PRACTICE IN THE STATE OF GEORGIA, WITH ALL ASSOCIATED COSTS BORNE BY THE CONTRACTOR. LIKEWISE ALL LANDSCAPING, STREET SIGNS, MAILBOXES, TRAFFIC SIGNS AND OTHER STREET FURNITURE DISTURBED BY CONSTRUCTION OPERATIONS SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION WITHOUT ADDITIONAL COMPENSATION.

WATER AND SEWER NOTES:

THE MINIMUM HORIZONTAL AND VERTICAL SEPARATION BETWEEN WATER LINES, SEWER LINES AND STORM DRAIN LINES SHALL CONFORM THE LATEST GEORGIA ENVIRONMENTAL PROTECTION GUIDELINES UNLESS NOTED OR OTHERWISE APPROVED BY THE ENGINEER.

PRESSURE AND LEAKAGE TESTING AND DISINFECTION OF NEW POTABLE WATER MAINS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH PROCEDURES DELINEATED IN THE PROJECT TECHNICAL SPECIFICATIONS.

WATER MAINS SHALL BE LAID WITH A MINIMUM COVER OF 42—INCHES IN PAVED AREAS AND 36—INCHES IN UNPAVED AREAS WITH AN ALLOWABLE MAXIMUM OF 60—INCHES. COVER IN ALL AREAS SHALL BE MEASURED FROM CROWN OF PIPE TO FINISH GRADE. A REDUCTION IN PIPE COVER REQUIREMENTS REQUIRES APPROVAL OF THE ENGINEER.

ALL NON-FLANGED FITTINGS AND VALVES SHALL BE RESTRAINED. THIS
SHALL BE ACCOMPLISHED USING MECHANICAL RESTRAINTS AT FITTINGS, AND
MECHANICAL RESTRAINT ALONG ADJACENT JOINTS OF PIPE IN ACCORDANCE
WITH DETAILS INCLUDED HEREIN.

THE CONTRACTOR SHALL FURNISH POTABLE WATER PIPING SYSTEMS AND APPURTENANCES, AND SANITARY SEWER PIPING AND APPURTENANCES IN ACCORDANCE WITH THE MATERIAL REQUIREMENTS CONTAINED IN THE PROJECT TECHNICAL SPECIFICATIONS. ALL MATERIALS SHALL BE NEW. ALL REFERENCES TO INDUSTRY STANDARDS (ASTM, ANSI, AWWA, ETC.) SHALL BE TO THE LATEST REVISION UNLESS STATED OTHERWISE.

ALL MATERIAL SHALL BE FREE FROM DEFECTS IMPAIRING STRENGTH AND DURABILITY AND SHALL BE OF THE BEST COMMERCIAL QUALITY FOR THE PURPOSE SPECIFIED.


THE CONTRACTOR SHALL INSPECT ALL MATERIALS DELIVERED TO THE JOBSITE FOR DAMAGE. MATERIALS SHALL BE UNLOADED AND STORED WITH A MINIMUM OF HANDLING. MATERIALS SHALL BE STORED ABOVE GROUND AND THE INTERIOR OF PIE AND FITTINGS SHALL BE KEPT FREE OF DIRT AND DEBRIS. STORE NON—METALLIC PIPING AND RUBBER GASKETS UNDER COVER AND PROTECT FROM EXPOSURE TO SUNLIGHT.


PRECAST CONCRETE MANHOLES AND OTHER APPURTENANCES SHALL BE HANDLED TO ENSURE DELIVERY AT THE POINT OF INSTALLATION IN SOUND, UNDAMAGED CONDITION. IF COATINGS OR LININGS OF PIPE OR FITTINGS ARE DAMAGED, SUCH PIPE AND FITTINGS SHALL BE REMOVED FROM THE SITE AND NEW MATERIALS FURNISHED.


ALL GRAVITY SEWER MAINS SHALL BE TESTED FOR LEAKAGE BY LOW PRESSURE AIR TESTING IN ACCORDANCE WITH THE PROJECT TECHNICAL SPECIFICATIONS. SUCH TESTING SHALL BE PERFORMED AS SOON AS POSSIBLE AFTER COMPLETING A REASONABLE LENGTH OF GRAVITY SEWER INSTALLATION.


No. 11257 EXPIRES DECEMBER 31, 201 N H 99 ヺヺ (J-1)


THIS DRAWING IS AN INSTRUMENT OF SERVICE AND REMAINS THE PROPERTY OF COASTAL ENGINEERING CONSULTANTS, INC. THIS DRAWING MAY NOT BE REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF COASTAL ENGINEERING CONSULTANTS,
































CALL BEFORE YOU DIG!

At least 72 hours prior to commencement of the work, the Contractor is responsible for calling the Utilities Protection Center (UPC) at 1-800-282-7411, to request underground utility locate service.

GRAPHIC SCALE	ري ا
0 50 100 150 1" = 50' HOR 1" = 5' VERT	FILE NO.: 2015-003-P
THIS DRAWING IS AN INSTRUMENT OF SERVICE AND REMAINS THE PROPERTY OF COASTAL ENGINEERING CONSULTANTS, INC. THIS DRAWING MAY NOT BE REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF COASTAL ENGINEERING CONSULTANTS, INC.	SHEET N

FILE NO.:

2015 STREETS, I

2015-003-P5

DATE:

MARCH 27, 2015

SCALE:

AS SHOWN


DRAWN BY/CHECKED BY:


CLITY OF WAYCROS!


CLM/NJH


STORM PIPE PROFILES - WALI


OWENS


























CHECKLIST ITEM NO. 1 THE APPLICABLE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN CHECKLIST ESTABLISHED BY THE COMMISSION AS OF JANUARY 1, 2015 HAS

LEVEL II CERTIFICATION NUMBER, SIGNATURE AND SEAL OF THE CERTIFIED DESIGN PROFESSIONAL APPERAS ON ALL EROSION AND SEDIMENT CONTROL

HE NAME AND 24-HOUR LOCAL CONTACT PERSON RESPONSIBLE FOR EROSION, SEDIMENTATION AND POLLUTION CONTROLS IS PROVIDED ELSEWHERE ON

CHECKLIST ITEM 4 THE NAME ADDRESS AND TELEPHONE NUMBER OF THE PRIMARY PERMITTEE IS PROVIDED ELSEWHERE ON THIS SHEET.

CHECKLIST ITEM 5 THE TOTAL AREA OF THE PROJECT IS 19.27 ACRES. THE TOTAL AREA TO BE DISTURBED BY THE MULTI—INFRASTRUCTURE IMPROVEMENTS IS

CHECKLIST ITEM & THE APPROXIMATE BEGINNING AND ENDING GPS COORDINATES OF THIS MULTI-INFRASTRUCTURE IMPROVEMENTS ARE AS FOLLOWS (SOURCE GOOGLE

WALKER STREET ENDING OWENS STREET BEGINNING OWENS STREET ENDING 31.2165° N 82.3674° W IZLAR STREET BEGINNING IZLAR STREET ENDING 31.2133° N 31.2163° N ROOSEVELT STREET BEGINNING 31.2148° N ROOSEVELY STREET ENDING

HECKLIST ITEM 7

CHECKLIST ITEM 9

THE INITIAL DATE OF THIS PLAN IS MARCH 27, 2015. ANY REVISIONS TO THIS PLAN AND THE ENTITY REQUESTING THE REVISIONS ARE SHOWN IN THE

THIS PROJECT INVOLVES THE CONSTRUCTION OF DRAINAGE IMPROVEMENTS, WATER DISTRIBUTION SYSTEM IMPROVEMENTS, SANITARY SEWER SYSTEM IMPROVEMENTS, STREET AND PAVEMENT IMPROVEMENTS ON WALKER, OWENS, IZLAR AND ROOSEVELT STREETS. THE PROJECT AREA IS BORDERED ON THE WEST BY SEAMAN STREET AND ON THE EAST BY NICHOLLS

A VICINITY MAP OF THE PROJECT AREA AND SURROUNDING AREAS IS SHOWN IN THE UPPER RIGHT HAND CORNER OF THIS SHEET.

THE ULTIMATE RECEIVING WATERS FOR THE STORMWATER RUNOFF FROM THIS PROJECT IS A MAJOR DRAINAGE CANAL SOUTH OF THE PROJECT AREA WHICH FLOWS FROM SOUTHWEST TO NORTHEAST ACROSS THE CITY OF WAYCROSS DOWNTOWN AREA. RUNOFF ENTERS THIS CANAL THROUGH A NETWORK OF NEW AND EXISTING STORM WATER CONVEYANCE PIPES THROUGH A RESIDENTIAL AREA SOUTH OF THE PROJECT AREA.

THE DESIGN PROFESSIONAL'S CERTIFICATION STATEMENT AND SIGNATURE THAT THE SITE WAS VISITED PRIOR TO DEVELOPMENT OF THE ES&PC IS

THE DESIGN PROFESSIONAL'S CERTIFICATION STATEMENT AND SIGNATURE THAT THE PERMITTEE'S ES&PC PLAN PROVIDES FOR AN APPROPRIATE AND

COMPREHENSIVE SYSTEM OF BMP'S AND SAMPLING TO MEET PERMIT REQUIREMENTS AS STATED ON PAGE 15 OF THE PERMIT IS INCLUDED ELSEWHERE ON THIS SHEET.

THE DESIGN PROFESSIONAL'S CERTIFICATION STATEMENT AND SIGNATURE THAT THE PERMITTEE'S ES&PC PLAN PROVIDES FOR REPRESENTATIVE SAMPLING AS STATED ON PAGE 26 OF THE PERMIT IS NOT APPLICABLE TO THIS PROJECT.

THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT. THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS, PERIMETER CONTROL BMP'S, AND SEDIMENT BASINS (IF APPLICABLE) IN ACCORDANCE WITH PART IV.A.5 WITHIN SEVEN (7) DAYS AFTER INSTALLATION.

CHECKLIST ITEM 15 NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25-FOOT OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

AMENDMENTS OR REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMP'S WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES. CHECKLIST ITEM 19

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE. CHECKLIST ITEM 20

ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14—DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY

CHECKLIST ITEM 21 THIS ITEM IS NOT APPLICABLE TO THIS PROJECT.

CHECKLIST ITEM 22

THIS ITEM IS NOT APPLICABLE TO THIS PROJECT.

CHECKLIST ITEM 23 CONCRETE WASHDOWN OF TOOLS, CONCRETE MIXERS CHUTES, HOPPERS AND THE REAR OF VEHICLES, AS WELL AS WASHOUT OF THE DRUM AT THE CONSTRUCTION SITE IS PROHIBITED. CHECKLIST ITEM 24

PETROLEUM PRODUCTS EXPOSED TO STORM WATER RUNOFF ARE OF PARTICULAR CONCERN DUE TO THEIR POSSIBLE IMPACTS ON WETLAND HABITATS, WILDLIFE AND DRINKING WATER SUPPLIES. SOURCES OF PETROLEUM POLLUTION INCLUDE LEAKAGE FROM FUEL TANKS, DRUMS AND CANS AS WELL AS HEAVY CONSTRUCTION EQUIPMENT. ALL ON SITE VEHICLES SHALL BE MONITORED FOR LEAKS AND SHALL RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS SHALL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED AND LOCATED WITHIN SECONDARY CONTAINMENT SYSTEMS. ACCUMULATED RAINFALL AND STANDING WATER INSIDE SECONDARY CONTAINMENT SYSTEMS MAY BE CONTAMINATED AND SHOULD BE DISPOSED OF ACCORDINGLY. IN ADDITION TO GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES, THE FOLLOWING PROCEDURES SHALL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:

MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP SHALL BE CLEARLY POSTED AND SITE PERSONNEL MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.

MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP SHALL BE KEPT IN THE MATERIAL STORAGE AREA ON SITE, EQUIPMENT AND

MATERIALS INCLUDE BUT ARE NOT LIMITED TO BROOMS, MOPS, DUST PANS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.

THE SPILL AREA SHALL BE KEPT WELL VENTILATED AND PERSONNEL SHALL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE

SPILLS OF TOXIC OR HAZARDOUS MATERIALS SHALL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENTAL AGENCY REGARDLESS OF THE SPILL PREVENTION PLAN SHALL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO

CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY TO DAY SITE OPERATIONS SHALL BE THE DESIGNATED CLEAN UP COORDINATOR. AT LEAST THREE OTHER SITE PERSONNEL SHOULD RECEIVE SPILL PREVENTION AND CLEAN UP TRAINING

NO MEASURE ARE PROPOSED TO CONTROL STORM WATER POLLUTANTS OCCURRING AFTER CONSTRUCTION OPERATIONS HAVE BEEN COMPLETED EXCEPT AS DESCRIBED BELOW. STORMWATER RUNOFF FROM THE PROJECT AREA WILL NOT BE INCREASED AS A RESULT OF THESE MULTI—INFRASTRUCTURE MPROVEMENTS. NO STORM WATER DETENTION OR RETENTION STRUCTURES ARE PROPOSED. ALL DISTURBED AREAS (ROAD SHOULDERS) WILL BE RE-VEGETATED AND AFFECTED SIDEWALKS, DRIVEWAYS AND PAVEMENT SURFACES WILL BE RESTORED.

CHECKLIST ITEM 26 N ADDITION TO SEDIMENT FROM CONSTRUCTION ACTIVITIES, THE FOLLOWING MATERIALS OR SUBSTANCES ARE EXPECTED TO BE PRESENT ON THE SITE DURING CONSTRUCTION ACTIVITIES: CONCRETE, DETERGENTS, PAINTS, METAL STUDS, ASPHALT, CRUSHED STONE AND GRAVEL,TAR, FERTILIZERS, PETROLEUM PRODUCTS, CLEANING SOLVENTS, WOOD, MASONRY, ROOFING SHINGLES, ETC. AN EFFECTIVE SPILL PREVENTION PROGRAM DESIGNED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND POLLUTANTS TO STORM WATER RUNOFF SUCH AS GOOD HOUSEKEEPING PRACTICES AND SOUND MATERIAL MANAGEMENT PRACTICES MUST BE EMPLOYED. MATERIAL MANAGEMENT PRACTICES INCLUDE THE

STORE ONLY ENOUGH PRODUCT TO ACCOMPLISH THE JOB

. STORE ALL MATERIALS IN A NEAT ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND UNDER A ROOF OR OTHER ENCLOSURE

KEEP PRODUCTS IN THEIR ORIGINAL CONTAINER WITH THE ORIGINAL MANUFACTURER'S LABEL . DO NOT MIX SUBSTANCES WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER

. WHENEVER POSSIBLE, ALL OF A PRODUCT SHOULD BE USED BEFORE DISPOSING OF THE CONTAINER

FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL OF PRODUCTS

PERFORM DAILY INSPECTIONS OF MATERIAL STORAGE AREAS TO ENSURE PROPER USE, STORAGE AND DISPOSAL OF SUBSTANCES

FERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS RECOMMENDED BY THE MANUFACTURER AND WHEN ONCE APPLIED SHALL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORM WATER. ALL PAINT CONTAINERS SHALL BE TIGHTLY SEALED AND STORED WHEN NOT IN USE.

EXCESS PAINT AND WATER FROM CLEANUP OPERATIONS SHALL NOT BE DISCHARGED TO THE STORM WATER SYSTEM BUT DISPOSED OF ACCORDING TO IANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS. CONCRETE TRUCKS WILL NOT BE ALLOWED TO DISCHARGE SURPLUS CONCRETE OF DRUM WASH WATER ON THE SITE. SEE SUBSEQUENT PARAGRAPHS FOR DETAILED INFORMATION REGARDING PETROLEUM PRODUCTS AND SPILL CONTROL PRACTICES, SOLID WASTE DISPOSAL AND SANITARY WASTE DISPOSAL.

CHECKLIST ITEM 27 A CHART OR TIMELINE OF THE INTENDED SEQUENCE OF MAJOR CONSTRUCTION ACTIVITIES IS INCLUDED ELSEWHERE ON THIS SHEET. CHECKLIST ITEM 28

THE PRIMARY PERMITTEE'S COMPLETE REQUIREMENTS FOR INSPECTION AND MONITORING AREA AS FOLLOWS (THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED). FOR EACH DAY WHEN ANY TYPE OF CONSTRUCTION ACTIVITY HAS TAKEN PLACE AT THE PRIMARY PERMITTEES'S SITE, CERTIFIED PERSONNEL SHALL

(b) ALL LOCATIONS WHERE VEHCILES ENTER OR EXIT THE SITE FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING MEASURE RAINFALL ONCE EVERY 24-HOURS EXCEPT ANY NON-WORKING WEEKEND DAY OR FEDERAL HOLIDAY UNLESS ALL AREAS OF THE SITE HAVE HAVE UNDERGONE FINAL STABILIZATION IN WHICH CASE RAINFALL MEASUREMENT MAY BE SUSPENDED.

INSPECT: (a) ALL AREAS WHERE PETROLEUM PRODUCTS ARE USED STORED OR HANDLED FOR SPILLS AND LEAKS FROM VEHICLES AND EQUIPMENT;

3. CERTIFIED PERSONNEL SHALL INSPECT THE FOLLOWING AT LEAST ONCE EVERY 14-DAYS AND WITHIN 24-HOURS OF THE END OF A STORM THAT IS 0.5 INCHES RAINFALL OR GREATER (UNLESS SUCH STORM ENDS AFTER 5:00 PMON ANY NON-WORKING WEEKEND DAY OR FEDERAL HOLIDAY IN WHICH CASE THE INSPECTION SHALL BE COMPLETED BY THE END OF THE NEXT BUSINESS OR WORKING DAY WHICHEVER OCCURS FIRST): (a) DISTURBED AREAS OF THE CONSTRUCTION SITE: (b) AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION: (DISTORBED AREAS OF THE CONSTRUCTION SITE, (b) AREAS OSED FOR STOKAGE OF MATERIALS THAT ARE EAROSED TO FRECIFITATION, (c) STRUCTURAL CONTROL MEASURES EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS. FOR AREAS WHICH HAVE UNDERGONE FINAL STABILIZATION. THE PERMITTEE MUST COMPLY WITH PART IV.D.4.a(4).

CERTIFIED PERSONNEL SHALL INSPECT AT LEAST ONCE PER MONTH AREAS OF THE SITE THAT HAVE UNDERGONE FINAL STABILIZATION FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING DRAINAGE SYSTEM AND DOWNSTREAM RECEIVING WATERS. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS. FOR AREAS WHICH HAVE UNDERGONE FINAL STABILIZATION, THE PERMITTEE MUST COMPLY

5. BASED ON THE RESULTS OF EACH INSPECTION, THE ES&PC PLAN SHALL BE REVISED AS APPROPRIATE NOT LATER THAN 7 CALENDAR DAYS FOLLOWING THE INSPECTION. IMPLEMENTATION OF SUCH CHANGES SHALL BE MADE AS SOON AS PRACTICABLE BUT IN NO CASE LATER THAN 7 CALENDAR DAYS FOLLOWING THE INSPECTION.

6. A REPORT OF EACH INSPECTION THAT INCLUDES THE NAME(S) OF CERTIFIED PERSONNEL MAKING EACH INSPECTION, THE DATE(S) OF EACH INSPECTION, CONSTRUCTION PHASE, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE ES&PC PLAN, AND ACTIONS IN ACCORDANCE WITH PART IV.D.4.a.(5) OF THE PERMIT SHALL BE MADE AND RETAINED AT THE SITE OR BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION UNTIL THE ENTIRE SITE HAS UNDERGONE FINAL STABILIZATION AND A NOTICE OF TERMINATION IS SUBMITTED TO EPD. SUCH REPORTS SHALL BE AVAILABLE BY THE END OF THE SECOND BUSINESS OR WORKING DAY AND SHALL IDENTIFY ALL INCIDENTS OF BMP'S THAT HAVE NOT BEEN PROPERLY INSTALLED AND/OR MAINTAINED AS DESCRIBED IN THE PLAN. WHERE THE REPORT DOES NOT IDENTIFY ANY INCIDENTS. THE NSPECTION REPORT SHALL CONTAIN A STATEMENT THAT THE BMP'S ARE IN COMPLIANCE THE ES&PC PLAN. ALL REPORTS SHALL BE SIGNED IN ACCORDANCE WITH PART V.G.2 OF THE PERMIT.

THE PRIMARY PERMITTEE MUST SAMPLE IN ACCORDANCE WITH THE PLAN AT LEAST ONCE FOR EACH RAINFALL EVENT DESCRIBED BELOW. FOR A QUALIFYING EVENT THE PERMITTEE SHALL SAMPLE AT THE BEGINNING OF ANY STORM WATER DISCHARGE TO A MONITORED RECEIVING WATER AND/OR FROM A MONITORED OUTFALL LOCATION WITHIN 45 MINUTES OR AS SOON AS POSSIBLE. HOWEVER WHERE MANUAL OR AUTOMATIC SAMPLING ARE IMPOSSIBLE AS DEFINED IN THE PERMIT OR ARE BEYOND THE PERMITTEE'S CONTROL, SAMPLES SHALL BE TAKEN AS SOON AS POSSIBLE BUT IN NO CASE MORE THAN 12 HOURS AFTER THE BEGINNING OF THE STORM WATER DISCHARGE.

1. FOR EACH AREA OF THE SITE THAT DISCHARGES TO A RECEIVING WATER OR OUTFALL, THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCHES WITH A STORM WATER DISCHARGE THAT OCCURS DURING NORMAL BUSINESS HOURS AFTER ALL CLEARING OPERATIONS HAVE BEEN COMPLETED BUT PRIOR TO COMPLETION OF MASS GRADING OPERATIONS.

2. IN ADDITION TO ITEM 1 ABOVE, FOR EACH AREA OF THE SITE THAT DISCHARGES TO A RECEIVING WATER OR OUTFALL, THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCHES WITH A STORM WATER DISCHARGE THAT OCCURS DURING NORMAL BUSINESS HOURS EITHER 90 DAYS AFTER THE FIRST SAMPLING EVENT OR AFTER ALL MASS GRADING OPERATIONS HAVE BEEN COMPLETED WHICHEVER OCCURS FIRST

3. AT THE TIME OF SAMPLING PERFORMED PURSUANT TO ITEMS 1 AND 2 ABOVE, IF BMP'S IN ANY AREA OF THE SITE ARE NOT PROPERLY DESIGNED INSTALLED AND MAINTAINED, CORRECTIVE ACTION SHALL BE DEFINED AND IMPLEMENTED WITHIN 2 BUSINESS DAYS, AND TURBIDITY SAMPLES SHALL BE TAKEN FROM DISCHARGES FOR EACH SUBSEQUENT RAIN EVENT THAT REACHED OR EXCEEDS 0.5 INCHES DURING NORMAL BUSINESS HOURS UNTIL THE TURBIDITY STANDARD IS ATTAINED OR UNTIL POST STORM INSPECTIONS DETERMINE THAT BMP'S ARE PROPERLY DESIGNED,INSTALLED AND

4. WHERE SAMPLING PURSUANT TO ITEMS 1, 2 AND 3 ABOVE IS REQUIRED BUT NOT POSSIBLE (OR NOT REQUIRED BECAUSE THERE WAS NO DISCHARGE). THE INSPECTION REPORT MUST INCLUDE A WRITTEN JUSTIFICATION OF WHY SAMPLING WAS NOT PERFORMED.

SAMPLE RESULTS MUST BE SUBMITTED BY THE FIFTEENTH DAY OF THE MONTH FOLLOWING THE REPORTING PERIOD (MONTHS DURING WHICH SAMPLES ARE TAKEN) TO THE EPD AT THE FOLLOWING ADDRESS BY RETURN RECEIPT CERTIFIED MAIL. THE PERMITTEE SHALL RETAIN A COPY OF THE PROOF OS SUBMITTAL AT THE CONSTRUCTION SITE OR OTHER DESIGNATED LOCATION.

> COASTAL DISTRICT - BRUNSWICK OFFICE GEORGIA ENVIRONMENTAL PROTECTION DIVISION 400 COMMERCE CENTER DRIVE BRUNSWICK, GEORGIA 31523-8251

SAMPLE REPORTS MUST BE SIGNED AND SHALL INCLUDE THE FOLLOWING INFORMATION:

RAINFALL AMOUNT, DATE, EXACT PLACE AND TIME OF SAMPLING NAME(S) OF THE CERTIFIED PERSONNEL WHO PERFORMED THE SAMPLING AND THE ANALYSES DATE AND TIME ANALYSES WERE PERFORMED

REFERENCES AND WRITTEN PROCEDURES FOR THE ANALYTICAL TECHNIQUES USED RESULTS OF ANALYSES RESULTS INCLUDING BENCH SHEETS RESULTS WHICH EXCEED 1000 NTU SHALL BE REPORTED AS "EXCEEDS 1000 NTU"

CHECKLIST ITEM 30 THE PRIMARY PERMITTEE SHALL RETAIN THE FOLLOWING RECORDS AT THE CONSTRUCTION SITE OR AT A DESIGNATED ALTERNATE LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTIL SUCH TIME AS A NOTICE OF TERMINATION IS SUBMITTED.

1. A COPY OF ALL NOTICES OF INTENT

CHECKLIST ITEM 29

3. THE DESIGN PROFESSIONAL'S REPORT OF THE RESULTS OF THE INSPECTION REQUIRED UNDER CHECKLIST ITEM 14 ABOVE

4. A COPY OF ALL SAMPLING INFORMATION, RESULTS AND REPORTS REQUIRED BY THIS PERMIT

5. A COPY OF ALL INSPECTION REPORTS GENERATED IN ACCORDANCE WITH THIS PERMIT 6. A COPY OF ALL VIOLATION SUMMARIES AND VIOLATION SUMMARY REPORTS GENERATED IN ACCORDANCE WITH THIS PERMIT

7. DAILY RAINFALL INFORMATION COLLECTED IN ACCORDANCE WITH THIS PERMIT

COPIES OF ALL NOTICES OF INTENT, NOTICES OF TERMINATION, INSPECTION REPORTS, SAMPLING REPORTS OR OTHER REPORTS REQUESTED BY EPD, ES&PC PLANS AND ALL OTHER RECORDS REQUIRED BY THIS PERMIT SHALL BE RETAINED BY THE PERMITTEE FOR A PERIOD OF AT LEAST THREE YEARS FROM THE DATE THE NOTICE OF TERMINATION IS SUBMITTED. THESE RECORDS MUST BE MAINTAINED AT THE PRIMARY PERMITTEE'S PRIMARY PLACE OF BUSINESS OR DESIGNATED ALTERNATE LOCATION.

ALL SAMPLING SHALL BE COLLECTED BY "GRAB SAMPLES" AND THE ANALYSIS OF THESE SAMPLES MUST BE CONDUCTED IN ACCORDANCE WITH METHODOLOGY AND TEST PROCEDURES ESTABLISHED BY 40 CFR PART 136 (UNLESS OTHER PROCEDURES HAVE BEEN APPROVED); THE GUIDANCE DOCUMENT TITLED "NPDES STORM WATER SAMPLING GUIDANCE DOCUMENT, EPA 833-B-92-001" AND GUIDANCE DOCUMENTS THAT MAY BE PREPARED

1. SAMPLE CONTAINERS SHOULD BE LABELED PRIOR TO COLLECTING SAMPLES 2. SAMPLES SHOULD BE WELL MIXED BEFORE TRANSFERRING TO A SECONDARY CONTAINER

3. LARGE MOUTH, WELL CLEANED AND RINSED GLASS OR PLASTIC JARS SHOULD BE USED FOR COLLECTING SAMPLES. THE JARS SHOULD BE CLEANED

4. MANUAL, AUTOMATIC OR RISING STAGE SAMPLE MAY BE UTILIZED. SAMPLES REQUIRED BY THIS PERMIT SHOULD BE ANALYZED IMMEDIATELY, BUT IN CASE MORE THAN 48 HOURS AFTER COLLECTION. HOWEVER, SAMPLES FROM AUTOMATIC SAMPLERS MUST BE COLLECTED NO LATER THAN THE NEXT BUSINESS DAY AFTER THEIR ACCUMULATION, UNLESS FLOW THROUGH AUTOMATED ANALYSIS IS UTILIZED. IF AUTOMATIC SAMPLING IS UTILIZED AND THE AUTOMATIC SAMPLER IS NOT ACTIVATED DURING THE QUALIFYING EVENT, THE PERMITTEE MUST UTILIZE MANUAL SAMPLING OR RISING STAGE SAMPLING DURING THE NEXT QUALIFYING EVENT. DILUTION OF SAMPLES IS NOT REQUIRED. SAMPLES MAY BE ANALYZED DIRECTLY WITH A PROPERLY CALIBRATED TURBIDIMETER. SAMPLES ARE NOT REQUIRED TO BE COOLED.

5. SAMPLING AND ANALYSIS OF THE RECEIVING WATERS OR OUTFALLS BEYOND THE MINIMUM FREQUENCY STATED IN THIS PERMIT MUST BE REPORTED CHECKLIST ITEM 32

FOR A PROJECT AREA OF 1.25 DISTURBED ACRES AND "WATERS SUPPORTING WARM WATER FISHERIES" DRAINAGE AREA APPROXIMATELY 5 TO 9.99 SQUARE MILES IN SIZE, THE NTU VALUE TO USE IN PART III.D.4 IS 150 NTU.

A USGS TOPOGRAPHIC MAP IS SHOWN ELSEWHERE ON THIS SHEET SHOWNG BOTH THE LOCATION OF ALL PERENNIAL OR INTERMITTENT STREAMS (DRAINAGE CANALS) INTO WHICH STORM WATER FROM THE SITE IS ULTIMATELY DISCHARGED. ALSO SHOWN ARE THE TWO SAMPLING LOCATIONS COUTFALLS) SELECTED FOR THIS PROJECT. OUTFALL NO. 1 IS AN EXISTING GRATE INLET WHICH IS THE POINT OF CONNECTION FOR THE PROPOSED PIPING SYSTEM SERVING WALKER STREET, OWENS STREET AND PORTIONS OF ROOSEVELT STREET. OUTFALL NO. 2 IS AN EXISTING CURB INLET WHICH IS THE POINT OF CONNECTION FOR THE PROPOSED PIPING SYSTEM SERVING IZLAR STREET AND PORTIONS OF ROOSEVELT STREET. THE EXISTING DOWNSTREAM STORM WATER CONVEYANCES DISCHARGE TO THE DRAINAGE CANAL AT THE APPROXIMATE LOCATION SHOWN ON THE USGS MAP. THE SAMPLING LOCATIONS ARE ALSO INDICATED ON THE FOLLOWING EROSION CONTROL PLANS. CHECKLIST ITEM 34

STRUCTURAL BMP'S THAT WILL BE IMPLEMENTED INCLUDE, BUT ARE NOT LIMITED TO, SEDIMENT BARRIERS (SILT FENCES) AT SELECTED LOW POINTS TO SLOW THE VELOCITY OF SURFACE RUNOFF, CAUSE SEDIMENT DEPOSITION AT THE STRUCTURE AND FILTER SEDIMENT FROM RUNOFF; AND INLET SEDIMENT TRAPS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAINAGE SYSTEMS. VEGETATIVE BEST MANAGEMENT PRACTICES TO BE IMPLEMENTED AS APPROPRIATE INCLUDE DISTURBED AREA VEGETATION WITH MULCHING ONLY, TEMPORARY SEEDING AND PERMANENT VEGETATION. SINCE NO MASS GRADING OPERATIONS WILL BE PERFORMED AND THE INITIAL PERIMETER CONTROL BMP'S INTERMEDIATE GRADING AND DRAINAGE BMP'S AND FINAL BMP'S ARE ALL THE SAME, THE PLAN COMBINES ALL OF THE BMP'S INTO A SINGLE PHASE WHICH IS SHOWN ON PLAN SHEET ES-2.

A GRAPHIC SCALE AND NORTH ARROW IS SHOWN ON PLAN SHEET ES-2.

CHECKLIST ITEM 36

EXISTING AND PROPOSED CONTOUR LINES WILL BE THE SAME. PLAN SHEET ES-2 SHOWS SPOT ELEVATIONS AND OTHER APPROPRIATE TOPOGRAPHICAL CHECKLIST ITEM 37

THE USE OF ALTERNATIVE BMP'S ARE NOT PROPOSED FOR USE ON THIS PLAN. CHECKLIST ITEM 38

THERE ARE NO APPLICABLE 25 FOOT OR 50 FOOT UNDISTURBED BUFFERS APPLICABLE TO THIS PROJECT.

THERE ARE NO WETLANDS OR STATE WATERS LOCATED ON OR WITHIN 200 FEET OF THE PROJECT SITE.

CHECKLIST ITEM 40 THE PROJECT SITE IS LOCATED AT THE UPPER END OF THIS WATERSHED. THERE ARE NO CONTRIBUTING DRAINAGE BASINS ON THE PROJECT SITE.

CHECKLIST ITEM 41 THE ONSITE DRAINAGE AND OFFSITE WATERSHED IS SHOWN ON THE USGS TOPOGRAPHIC MAP INCLUDED ELSEWHERE ON THIS SHEET. CHECKLIST ITEM 42

THE RUNOFF FROM THE PROJECT AREA WILL NOT BE INCREASED AS A RESULT OF THIS PROJECT. THE ESTIMATED RUNOFF COEFFICIENT FOR CHECKLIST ITEM 43

STORM DRAIN PIPE SIZES, FLOWS AND VELOCITIES ARE SHOWN IN THE TABLE FLISHWHERE ON THIS SHEET, ALL PROPOSED STORM DRAIN PIPING SYSTEMS DISCHARGE TO EXISTING STORM INLETS WHICH COINCIDE WITH THE STORM WATER SAMPLING POINTS PREVIOUSLY IDENTIFIED. OUTLET PROTECTION TO PREVENT EROSION IS NOT REQUIRED.

SOIL SERIES TYPES AND APPROXIMATE DELINEATIONS ARE SHOWN ON PLAN SHEET ES-2. SOIL TYPES FOUND IN THE PROJECT AREA INCLUDE LEEFIELD LOAMY SAND (LdA) COVERING 71.4% OF THE PROJECT SITE AND PELHAM LOAMY FINE SAND (PmB) COVERING 28.6% OF THE PROJECT SITE. CHECKLIST ITEM 45

THE LIMITS OF DISTURBANCE ARE SHOWN ON PLAN SHEET ES-2.

THE REQUIRED SEDIMENT STORAGE IS 67 CUBIC YARDS PER ACRE DISTURBED, OR IN THIS CASE 1.25 ACRES TIMES 67 EQUALS 84 CUBIC YARDS. A SEDIMENT STORAGE BASIN IS NOT ATTAINABLE FOR THIS SITE NOR IS ONE NEEDED SINCE NO MASS GRADING OPERATIONS ARE PROPOSED. THE PROPOSED BMP'S CONSISTING OF SEDIMENT BARRIERS AND INLET SEDIMENT TRAPS ARE CONSIDERED SUFFICIENT BY THE DESIGN PROFESSIONAL AS

PLAN SHEET ES-2 SHOWS THE LOCATION OF STRUCTURAL AND VEGETATIVE BMP'S THAT ARE CONSISTENT WITH AND NO LESS STRINGENT THAN THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA USING THE UNIFORM CODING SYMBOLS FROM THE MANUAL, CHAPTER 6, WITH LEGEND.

DETAILED DRAWINGS FOR ALL STRUCTURAL PRACTICES ARE SHOWN ON PLAN SHEET ES-4. A VEGETATIVE PLAN NOTING ALL TEMPORARY AND

VEGETATIVE PRACTICES IS SHOWN ON PLAN SHEET ES-3. THE PLAN INCLUDES SPECIES, PLANTING DATES AND SEEDING, FERTILIZER LIME AND

MULCHING RATES. THE PLAN IS SITE SPECIFIC FOR THE APPROPRIATE TIME OF YEAR THAT SEEDING WILL TAKE PLACE AND FOR THE APPROPRIATE

CEORDADHIC BECIDIN OF CEORGIA.

PIPE NUMBER	PIPE SIZE (INCHES)	PIPE TYPE	COEFFICIENT "C"	DESIGN FLOW (CFS)	SLOPE (FT/FT)	VELOCITY @ DESIGN FLOW (FPS)	DEPTH OF FLOW (INCHES)
			PIPE SYSTEI	l M NUMBER 1		(113)	(INCITES)
W1	15	HDPE	0.010	0.55	0.0100	3.05	3.05
W2	15	HDPE	0.010	1.34	0.0050	3.21	5.58
W3	15	HDPE	0.010	0.56	0.0100	3.08	3.10
W4	15	HDPE	0.010	2.70	0.0050	4.05	8.02
W5	15	HDPE	0.010	1.16	0.0040	2.85	5.50
W6	15	HDPE	0.010	0.42	0.0100	2.81	2.70
R1	15	HDPE	0.010	0.45	0.0100	2.86	2.77
R2	15	HDPE	0.010	0.85	0.0050	2.77	4.46
R3	18	HDPE	0.010	4.71	0.0040	4.34	10.63
R4	15	HDPE	0.010	0.53	0.0100	3.01	3.00
R5	18	HDPE	0.010	5.69	0.0040	4.62	11.84
01	15	HDPE	0.010	0.39	0.0100	2.74	2.60
02	15	HDPE	0.010	1.05	0.0050	2.97	4.95
03	15	HDPE	0.010	0.62	0.0100	3.18	3.25
04	15	HDPE	0.010	2.52	0.0050	3.96	7.73
05	24	HDPE	0.010	8.21	0.0025	4.19	14.36
06	15	HDPE	0.010	0.60	0.0100	3.15	3.20
07	24	HDPE	0.010	9.54	0.0025	4.40	15.65
08	15	HDPE	0.010	0.49	0.0100	2.95	2.90
09	24	RCP	0.013	10.63	0.0025	3.80	20.03
010	24	RCP	0.013	10.63	0.0025	3.80	20.03
			PIPE SYSTEM	NUMBER 2			
/1	15	HDPE	0.010	0.52	0.0100	2.99	2.97
12	15	HDPE	0.010	1.15	0.0050	3.06	5.18
/3	15	HDPE	0.010	0.41	0.0100	2.78	2.65
14	15	HDPE	0.010	2.13	0.0050	3.74	7.07
15	18	HDPE	0.010	4.33	0.0021	3.40	12.20
16	15	HDPE	0.010	0.47	0.0100	2.91	2.85
17	18	HDPE	0.010	5.44	0.0021	3.65	14.15
18	15	HDPE	0.010	0.50	0.0050	2.97	2.94
19	21	RCP	0.013	6.56	0.0016	2.83	19.31
110	15	HDPE	0.010	0.50	0.0050	2.97	2.94
/11	21	RCP	0.013	6.56	0.0016	2.83	19.31
R6	15	HDPE	0.010	0.55	0.0100	3.05	3.05
R7	15	HDPE	0.010	0.93	0.0050	2.85	4.66
R8	15	HDPE	0.010	0.43	0.0100	2.83	2.73
R9	15	HDPE	0.010	1.27	0.0025	2.80	<i>5.95</i>

PROJECT TIMELINE

ACTIVITY

DEMOLITION OF EXISTING CURBING AND STORM DRAINS

CONSTRUCT NECESSARY BASE AND SUBGRADE REPAIRS

CONSTRUCT NEW WATER DISTRIBUTION SYSTEM

CONSTRUCT NEW SANITARY SEWER SYSTEM

REMOVAL OF BMP'S AND FINAL STABILIZAION

CONSTRUCT NEW STORM DRAIN SYSTEM


INSTALL NEW CURB AND GUTTER


RESURFACE STREETS

INSTALL INITIAL BMP'S

MILL EXISTING ASPHALT SURFACES

WEEKS FROM NOTICE TO PROCEED





DESIGN PROFESSIONAL'S STATEMENTS: TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THE PERMITTEE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE GEORGIA WATER QUALITY ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" (MANUAL) PUBLISHED BY THE STATE SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND-DISTURBING ACTIVITY WAS PERMITTED, PROVIDES FOR THE SAMPLING OF THE RECEIVING WATER(S) OR THE SAMPLING OF THE STORM WATER OUTFALLS AND

THAT THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET THE REQUIREMENTS

II CERTIFIED DESIGN PROFESSIO

0

0

RO

SWCC CERTIFICATION NO. 00000262

B

CONTAINED IN THE GENERAL NPDES PERMIT NO. GAR 100002. COASTAL ENGINEERING CONSULTANTS, INC.

DATE NORBERT JOHN HUNKELE, JR. P.E. LEVEL II CERTIFIED DESIGN PROFESSIONAL GSWCC CERTIFICATION # 0000026209 AS MANDATED BY LAW AND AS THE PLAN DESIGNER, I HAVE VISITED THIS SITE PRIOR TO THE DESIGN OF THIS EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN.

COASTAL ENGINEERING CONSULTANTS, INC. NORBERT JOHN HUNKELE, JR. P.E.

LEVEL II CERTIFIED DESIGN PROFESSIONAL GSWCC CERTIFICATION # 0000026209 OWNER'S STATEMENT:

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURI THAT QUALIFIED PERSONNEL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING INFORMATION. THE INFORMATION SUBMITTED IS. TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR

KNOWNG VIOLATIONS. CITY OF WAYCROSS, GEORGIA

JESSICA KING-DEAL

NAME AND PHONE NUMBER OF 24-HOURCONTACT PERSON JESSICA-KING DEAL (912) 287–2945 GENE THOMAS


(912) 287-2944 NAME ADDRESS AND PHONE NUMBER OF PRIMARY PERMITTEE CITY OF WAYCROSS 417 PENDLETON STREET

INDEX OF DRAWINGS

WAYCROSS, GEORGIA 31502

(912) 287-0099

SHEET ES-1 | EROSION CONTROL GENERAL NOTES SHEET ES-2 | EROSION CONTROL PLAN SHEET ES-3 VEGETATIVE PLAN & UNIFORM CODING SYSTEM SHEET ES-4 DETAILS OF STRUCTURAL BMP'S




PROPERTY OF COASTAL ENGINEERING CONSULTANTS, INC. THIS DRAWING MAY NOT BE REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF COASTAL ENGINEERING CONSULTANTS,

At least 72 hours prior to commencement of the work, the Contractor is responsible for calling the Utilities Protection Center (UPC) at 1-800-282-7411, to request underground utility locate service. ACTION MARCH 27, 2015 RELEASED FOR CLIENT AND EPD PLAN REVIEW (NOT FOR CONSTRUCTION

DATE

THIS DRAWING IS AN INSTRUMENT OF SERVICE AND REMAINS THE HEET NO.



	TAB	LE 1 - VEGET	TATIVE PLAN			TABLE	4 — FERTILIZER REQUIR	REMENTS FOR TEM	PORARY VEGETATIO	»N
	DISTURBED AREA	STABILIZATION W	VITH MULCHING O	NLY — Ds1				<i>FERTILIZER</i>	RATE	N TOP DRESSING
MA	TERIAL		RATE		DEPTH	TYPES OF SPECIES	PLANTING YEAR	(N-P-K)	(LBS./ACRE)	RATE (LBS./ACRE)
STRA	W OR HAY		2.5 TONS/ACRE		6" TO 10"					
WOOD WASTE, CH	HIPS, SAWDUST, BARK		6 TO 9 TONS PER ACRE		2" TO 3"	COOL SEASON GRASSES	FIRST SECOND	6-12-12 6-12-12	1500 1000	50-100 -
CUTBA	CK ASPHALT	120	00 GAL/ACRE OR 0.25 GAL,	/sy	-		MAINTENANCE FIRST	10-10-10 6-12-12	400 1500	30 0–50
POLYET	HYLENE FILM	SECU	RE WITH SOIL, ANCHORS, WE	EIGHTS	-	COOL SEASON GRASSES & LEGUMES	SECOND MAINTENANCE	0-12-12 0-10-10 0-10-10	1000 400	- - -
GEOTEXTILES, JUTE	MATTING, NETTING, INC.	SEE M.	ANUFACTURER'S RECOMMEND	DA TIONS	-	TEMPORARY COVER CROPS SEEDED ALONE	FIRST	10-10-10	500	30
DEFINITION: A TEMPORARY CO	VER OF PLANT RESIDUES APPLIED TO			LESS WHEN SEEDING IS NO	OT PRACTICAL	WARM SEASON GRASSES	FIRST SECOND MAINTENANCE	6-12-12 6-12-12 10-10-10	1500 800 400	50–100 50–100 30
	TAB:	LE 2 – VEGET	TATIVE PLAN			TABLE	5 — FERTILIZER REQUIF	REMENTS FOR PER	MANENT VEGETATIC)N
	DISTURBED AREA ST			TEDING — Ds2 TING DATES BY F	REGION	TYPES OF SPECIES	PLANTING YEAR	FERTILIZER (N-P-K)	RATE (LBS./ACRE)	N TOP DRESSING RATE (LBS./ACRE)
SPECIES	RATE PER 1000 SF	RATES PER ACRE								
			M-L	Р	С	COOL SEASON GRASSES	FIRST SECOND	6-12-12 6-12-12	1500 1000	50-100 -
RYE (GRAIN)	3.9 LBS.	3 BU.	AUG 15 — NOV 19	SEPT 15 - DEC 1 MAR 1 - APR1	OCT 1 - NOV 1		MAINTENANCE FIRST	10-10-10	400	30
RYEGRASS	0.9 LBS.	40 LBS.	AUG 15 - NOV 15	SEPT 1 — DEC 15	SEPT 15 — JAN 1	COOL SEASON GRASSES & LEGUMES	SECOND MAINTENANCE	6-12-12 0-10-10 0-10-10	1500 1000 400	0–50 – –
RYE	0.6 LBS.	0.5 BU.	MAR 1 — APR 1	MAR 1 — APR 1	FEB 1 — MAR 1	WARM SEASON GRASSES	FIRST SECOND	6-12-12 6-12-12	1500 800	50-100 50-100
ANNUAL LESPEDEZA	0.6 LBS.	24 LBS.	MAR 1 —APR 1	MAR 1 — APR 1	FEB 1 — MAR 1		MAINTENANCE	10-10-10	400	30
WEEPING LOVEGRASS	0.1 LBS.	4 LBS.	APR 1 — JUNE 1	APR 1 — JUNE 1	MAR 1 — JUNE1	WARM SEASON GRASSES AND LEGUMES	FIRST SECOND MAINTENANCE	6-12-12 0-10-10 0-10-10	1500 800 400	50 - -
SUDANGRASS	1.0 LBS.	60 LBS.	MAY 1 — AUG 1	MAY 1 - AUG 1	APR 1 - AUG 1		TABLE 6 - SUGGESTED	SEEDBED DEPTHS	•	•

TABLE 3 - VEGETATIVE PLAN

SLOPES 3:1 OR FLATTER

SLOPES 2:1 OR STEEPER

SLOPES 2:1 TO 3:1

APR 15 - JULY 1

OCT 15 - JAN 1

DISTURBED AREA STABILIZATION WITH PERMANENT VEGETATION — Ds3

SPECIES	RATES PER ACRE	RATES PER 1000 SF	PLAN	ITING DATES BY R	REGION	REMARKS
'			M-L	Р	С	7
BAHIA, PENSACOLA			-	APR 1 TO MAY 31	MAR 1 TO MAY 31	LOW GROWING; SOD PRODUCING; WILL SPREAD INTO BERMUDA LAWNS
ALONE OR WITH TEMPORARY COVER	60 LBS	1.4 LBS	· ·	,		7
WITH OTHER PERENNIALS	30 LBS	0.7 LBS				7
BAHIA, WILMINGTON			MAR 15 TO MAY 31	MAR 1 TO MAY 31	-	LOW GROWING; SOD PRODUCING; WILL SPREAD INTO BERMUDA LAWNS
ALONE OR WITH TEMPORARY COVER	60 LBS	1.4 LBS				7
WITH OTHER PERENNIALS	30LBS	0.7 LBS				<u></u>
BERMUDA COMMON (HULLED SEED)			-	APR 1 TO MAY 31	MAR 15 TO MAY 31	QUICK COVER;LOW GROWING; SOD FORMING; NEEDS FULL SUN
ALONE	10LBS	0.2 LBS				7
WITH OTHER PERENNIALS	6LBS	0.1 LBS				<u> </u>
BERMUDA COMMON (UNHULLED SEED)			-	OCT 15 TO FEB 28	NOV 1 TO JAN 31	
WITH TEMPORARY COVER	10 LBS	0.2 LBS				PLANT WITH WINTER ANNUALS
WITH OTHER PERENNIALS	6 LBS	0.1 LBS				PLANT WITH TALL FESCUE
CROWN VETCH						MIX WITH 30 LBS TALL FESCUE OR 15 LBS RYE; INNOCULATE SEED; PLANT ONLY NORTH OF ATLANTA
WITH WINTER ANNUALS OR COOL SEASON GRASSES	15 LBS	0.3 LBS	SEPT 1 TO OCT 15	SEPT 1 TO OCT 15	-	<u> </u>
FESCUE, TALL						MIX WITH PERENNIAL LESPEDEZAS OR CROWN VETCH; NOT FOR DROUGHTY SOILS OR HEAVY USE AREAS
ALONE	50 LBS	1.1 LBS	MAR 1 TO APR 1	AUG 15 TO OCT 15		7
WITH OTHER PERENNIALS	30 LBS	0.7 LBS	AUG 15 TO SEPT 30	OR FEB 15 TO APR 15	-	
LESPEDEZA, SERICEA						WIDELY ADAPTED AND LOW MAINTENANCE; TAKES 2 TO 3 YEARS TO ESTABLISH; INOCULATE SEED WITH EL INOCULATE; MIX WITH WEEPING LOVEGRASS, COMMON BERMUDA, BAHIA OR TALL FESCUE
SCARIFIED	60 LBS	1.4 LBS	APR 1 TO MAY 31	MAR 15 TO MAY 31	MAR 1 TO MAY 15	- EL INDUDLATE; MIX WITH WEEPING LOVEGIAGO, COMMON BERMODA, DATING ON THE TESSE
UNSCARIFIED	75 LBS	1.7 LBS	SEPT 1 TO FEB 28	SEPT 1 TO FEB 28	SEPT 1 TO FEB 28	MIX WITH TALL FESCUE OR WINTER ANNUALS
SEED-BEARING HAY	3 TONS	138 LBS	OCT 1 TO FEB 1	OCT 1 TO FEB 1	SEPT 15 TO JAN 15	CUT WHEN SEED IS MATURE BUT BEFORE IT SHATTERS. ADD TALL FESCUE OR WINTER ANNUALS
LESPEDEZA, AMBRO VIRGATO OR APPALOW						SPREADING GROWTH WITH HEIGHT OF 18" TO 24"; GOOD IN URBAN AREAS; SLOW TO DEVELOP GOOD STANDS; MIX WITH WEEPING LOVEGRASS, COMMON BERMUDA, BAHIA, TALL FESCUE OR WINTER ANNUALS,
SCARIFIED	60 LBS	1.4 LBS	APR 1 TO MAY 31	MAR 15 TO MAY 31	MAR 1 TO MAY 15	DO NOT MIX WITH WEEPING LOVEGRASS, COMMON BERMUDA, BAHIA, TALL FESCUE OR WINTER ANNUALS, DO NOT MIX WITH SERICEA LESPEDEZA; INOCULATE SEED WITH EL INOCULANT
UNSCARIFIED	75 LBS	1.7 LBS	SEPT 1 TO FEB 28	SEPT 1 TO FEB 28	SEPT 1 TO FEB 28	<u> </u>
LOVEGRASS, WEEPING						QUICK COVER; DROUGHT TOLERANT; GROWS WELL WITH SERICEA LESPEDEZA ON ROAD BANKS AND OTHER STEEP SLOPES; SHORT LIVED
ALONE	4 LBS	0.1 LBS	APR 1 TO MAY 31	MAR 15 TO MAY 31	MAR 1 TO MAY 31	THEN SILLI SLOTES, SHOW LIVED
WITH OTHER PERENNIALS	2 LBS	0.05 LBS	APR 1 TO MAY 31	MAR 15 TO MAY 31	MAR 1 TO MAY 31	<u></u>
MAIDENCANE SPRIGS	2' BY 3'	3' SPACING	FEB 1 TO MAR 31	FEB 1 TO MAR 31	FEB 1 TO MAR 31	FOR VERY WET SITESSUCH AS RIVER BANKS AND SHORELINES; DIG SPRIGS LOCALLY
PANICGRASS, ATLANTIC COASTAL	20 LBS	50 LBS	-	MAR 1 TO APR 30	MAR 1 TO APR 30	GROWS WELL ON COASTAL SAND DUNES; MIX WITH SERICEA LESPEDEZA BUT NOT ON SAND DUNES
REED CANARY GRASS						GROWS SIMILAR TO TALL FESCUE; FOR WET SITES
ALONE	. 50 LBS	1.1 LBS	AUG 15 TO OCT 15	SEPT 1 TO OCT 15	-	
WITH OTHER PERENNIALS	30 LBS	0.7 LBS	AUG 15 TO OCT 15	SEPT 1 TO OCT 15	_	<u> </u>
SUNFLOWER, AZTEC MAXIMILLIAN	10 LBS	0.2 LBS	APR 15 TO MAY 31	APR 15 TO MAY 31	APR 1 TO MAY 31	MIX WITH WEEPING LOVEGRASS OR OTHER LOW GROWING GRASSES OR LEGUMES
SWITCHGRASS	20 LBS	0.4 LBS	APR 1 TO MAY 31	APR 1 TO MAY 31	APR 1 TO MAY 31	FOR STREAM BANK PLANTINGS, DRAINAGE DITCHES AND WET AREAS

EFINITION: APERMANENT VEGETATIVE COVER USING GRASSES, TREES, SHRUBS OR LEGUMES ON HIGHLY ERODIBLE OR CRITICALLY ERODED LANDS

<u> DISTURBED AREA STABILIZATION WITH MULCHING ONLY — Ds1</u> TEMPORARY COVER OF PLANT RESIDUES APPLIED TO THE SOIL SURFACE FOR A PERIOD OF SIX (6) MONTHS OR LESS WHEN SEEDING IS NOT PRACTICAL.

- REDUCE RUNOFF, EROSION AND SEDIMENTATION
- PREVENT SURFACE COMPACTION AND CRUSTING CONTROL UNDESIRABLE VEGETATION

BROWNTOP MILLET

WHFAT

1.1 LBS.

4.1 LBS.

50 LBS.

3 BU.

DEFINITION: A TEMPORARY VEGETATIVE COVER WITH FAST GROWING SEEDINGS FOR UP TO A 12 MONTH PERIOD OR UNTIL PERMANENT VEGETATIVE COVER IS ESTABLISHED.

APR 15 - JUNE 15

SEPT 15 — DEC 1

APR 15 - JULY 1

OCT 15 - DEC 15

- INSTALL ALL OTHER REQUIRED BMP'S FIRST GRADE SITE, IF POSSIBLE, TO PERMIT THE USE OF EQUIPMENT FOR APPLYING AND
- LOOSEN COMPACTED SOIL, IF POSSIBLE, TO A DEPTH OF 3-INCHES
- APPLY STRAW OR HAY UNIFORMLY, AS SHOWN IN TABLE ABOVE, BY HAND, AND ANCHOR BY PRESSING INTO SOIL
- MULCH ON SLOPES GREATER THAN 3% SHOULD BE ANCHORED WITH EMULSIFIED
- ASPHALT (GRADE AE-5 OR SS-1) OR OTHER SUITABLE TACKIFIER WOOD WASTE ON SLOPES FLATTER THAN 3:1 DO NOT NEED ANCHORING

ADD MULCH AS NEEDED TO MAINTAIN THE SUGGESTED DEPTH IF ORGANIC MULCH IS TO BE LEFT AND INCORPORATED INTO THE SOIL, APPLY 20 TO 30 POUNDS OF NITROGEN IN ADDITION TO THE FERTILIZER REQUIRED FOR

<u>DISTURBED AREA STABILIZATION WITH TEMPORARY SEEDING - Ds2</u> A TEMPORARY VEGETATIVE COVER WITH FAST GROWING SEEDINGS FOR UP TO A 12 MONTH PERIOD OR UNTIL PERMANENT VEGETATION IS ESTABLISHED.

- REDUCE RUNOFF, EROSION AND SEDIMENTATION
- IMPROVE WILDLIFE HABITAT IMPROVE AESTHETICS
- IMPROVE TILTH AND ORGANIC MATTER
- INSTALL ALL EROSION CONTROL MEASURES PRIOR TO APPLYING TEMPORARY
- GRADING OR SHAPING IS NOT REQUIRED IF SLOPES CAN BE PLANTED WITH A HYDROSEEDER OR BY HAND-SEEDING
- SEEDBED PREPARATION IS NOT REQUIRED IF SOIL IS LOOSE AND NOT SEALED BY
- WHEN SOIL IS SEALED OR CRUSTED, IT SHOULD BE PITTED, TRENCHED OR SCARIFIED TO PROVIDE A PLACE FOR SEED TO LODGE OR GERMINATE AGRICULTURAL LIME IS NOT REQUIRED
- FERTILIZER IS NOT REQUIRED ON FAIRLY FERTILE SOILS FERTILIZE LOW FERTILITY SOILS BY ADDING AND MIXING INTO SOIL PRIOR TO PLANTING AT THE RATE OF 500 - 700 POUNDS PER ACRE OF 10-10-10 FERTILIZER OR EQUIVALENT (12-16 POUNDS PRE 1000 SQUARE FEET)
 APPLY SEED BY HAND. CYCLONE SEEDER, DRILL OR HYDROSEEDER. SEED PLANTED
- SELECT A TEMPORARY COVER FROM THE TABLE 2 ABOVE.
- RE-SEED AREAS WHERE AN ADEQUATE STAND OF TEMPORARY VEGETATION FAILS TO EMERGE OR WHERE A POOR STAND EXISTS.

A PERMANENT VEGETATIVE COVER USING GRASSES, TREES, SHRUBS OR LEGUMES ON HIGHLY ERODIBLE OR CRITICALLY ERODED LANDS.

- REDUCE RUNOFF AND EROSION IMPROVE WILDLIFE HABITAT
- IMPROVE AESTHETICS IMPROVE TILTH AND ORGANIC MATTER REDUCE DOWNSTREAM COMPLAINTS REDUCE LIKELIHOOD OF LEGAL ACTION
- REDUCE LIKELIHOOD OF WORK STOPPAGE DUE TO LEGAL ACTION INCREASE "GOOD NEIGHBOR" BENEFITS

LESS THAN 4-INCHES DEPTH

DEPRESSIONS EVERY 6 TO 8 INCHES HAND DUG IF NECESSARY

USE CONVENTIONAL PLANTING METHODS WHEN POSSIBLE

SCARIFY, PIT OR TRENCH SEALED OR CRUSTED SOIL FERTILIZE BASED ON SOIL TESTS OR AS SHOWN IN TABLE 5 ABOVE APPLY AGRICULTURAL LIME AS PRESCRIBED BY SOIL TESTS OR AT A RATE OF 1 TO 2 TONS PER ACRE

REFER TO TABLE 3 ABOVE FOR SPECIES APPROPRIATE TO THIS REGION

WITH A DRILL SHOULD BE PLANTED 0.5 TO 1 INCH DEEP.

APPLY SEED BY HAND, CYCLONE SEEDER, DRILL OR HYDROSEEDER. SEED PLANTED WITH A DRILL SHOULD BE PLANTED 0.5 TO 1 INCH DEEP IRRIGATION SHOULD BE USED TO SUPPLEMENT RAINFALL, BUT NOT TO THE EXTENT

GEORGIA UNIFORM CODING SYSTEM

FOR SOIL EROSION AND SEDIMENT CONTROL PRACTICES

GEORGIA SOIL AND WATER CONSERVATION COMMISSION

STRUCTURAL PRACTICES

DOWNDRAIN STRUCTURE

PFRMANFN1

DOWNDRAIN STRUCTURE

FILTER RING

GABION

GRADE STABILIZATION STRUCTURE

SPREADER

RETAINING

SEEP BERM

▶ other material designed to safely conduct

and inexpensive.

surface runoff down a slope. This is tempore

A paved chute, pipe, sectional conduit or

similar material designed to safely conduct

A temporary stone barrier constructed at

Rock filter baskets which are hand-placed into position forming soil stabilizing

channels or waterways where otherwise the slope would be sufficient for the running

A structure to convert concentrated flow of

A permanent or temporary stone filter dam

water into less erosive sheet flow. This should be constructed only on undisturbed

installed across small streams or

A wall installed to stabilize cut and fill slope where maximum permissible slopes are not

obtainable. Each situation will require special

A device or structure placed in front of a permanent stormwater detention pond outlet

structure to serve as a temporary sediment

A barrier to prevent sediment from leaving the construction site. It may be sandbags, bales of straw or hay, brush, logs and poles

An impounding area created by excavating

excavated area will be filled and stabilized or completion of construction activities. (Sa3) A basin created by excavation or a dam across a waterway. The surface water runoff across a waterway. The surface water runoff is temporarily stored allowing the bulk of the sediment to drop out.

> A small temporary pond that drains a disturbed area so that sediment can settle

temporary sediment trap from a temporary sediment basin is the lack of a pipe or riser

A buoyant device that releases/drains water

out. The principle feature distinguishing a

from the surface of sediment ponds, traps, or basins at a controlled rate of flow.

Linear control device constructed as a diversion perpendicular to the direction of

runoff to enhance dissipation and infiltration,

with the employment of intermediate dikes.

gravel, or a silt fence.

sediment to drop out.

An impounding area created by excavarance around a storm drain drop inlet. The excavated area will be filled and stability completion of construction activities.

storm drain inlets and pond outlets.

surface runoff down a slope.

CODE PRACTICE DETAIL MAP SYMBOL DESCRIPTION A small temporary barrier or dam constructe Sr A temporary bridge or culvert—type **TEMPORARY** structure protecting a stream or watercours across a swale, drainage ditch or area of CHECKDAM STREAM from damage by crossing construction concentrated flow. CROSSING (St) A paved or short section of riprap channel nproving, constructing or stabilizing an ope STORMDRAIN at the outlet of a storm drain system channel, existing stream, or ditch. STABILIZATION preventing erosion from the concentrated PROTECTION A rough soil surface with horizontal construction site exit to provide a place for CONSTRUCTION SURFACE depressions on a contour or slopes left in removing mud from tires thereby protecting ROUGHENING roughened condition after grading. A travelway constructed as part of a (Tc) A floating or staked barrier installed within CONSTRUCTION construction plan including access roads, subdivision roads, parking areas and other the water (it may also be referred to as a CURTAIN STABILIZATION floating boom, silt barrier, or silt curtain). on-site vehicle transportation routes. The practice of stripping off the more fertile A temporary channel constructed to convey soil, storing it, then spreading it over the flow around a construction site while a DIVERSION **TOPSOILING** disturbed area after completion of permanent structure is being constructed (SHOW STRIPING AND CONSTRUCTION activities. An earth channel or dike located above, bel To protect desirable trees from injury during DIVERSION or across a slope to divert runoff. This ma construction activity. **PROTECTION** be a temporary or permanent structure. VEGETATED A flexible conduit of heavy—duty fabric or WATERWAY Paved or vegetative water outlets for TEMPORARY

STORMWATER

VECETATIVE DDACTICES

diversions, terraces, berms, dikes or similar

structures.


STRUCTURAL PRACTICES

	VI	EGETAT	IVE P	PRACTICES
CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Bf	BUFFER ZONE		Bf (LABEL)	Strip of undisturbed original vegetation, enhanced or restored existing vegetation or the reestablishment of vegetation surrounding an area of disturbance or bordering streams.
Cs	COASTAL DUNE STABILIZATION (WITH VEGETATION)	Jest to the state of the state	Cs	Planting vegetation on dunes that are denuded artificially constructed, or re—nourished.
Ds1	DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)		Ds1	Establishing temporary protection for disturbed areas where seedlings may not have a suitable growing season to produce an erosion retarding cover.
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP SEEDING)		Ds2	Establishing a temporary vegetative cover with fast growing seedings on disturbed areas.
Ds3	DISTURBED AREA STABILIZATION (WITH PERM SEEDING)	W. W. G. W. G. W.	Ds3	Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.
Ds4	DISTURBED AREA STABILIZATION (SODDING)		Ds4	A permanent vegetative cover using sods on highly erodable or critically eroded lands.
Du	DUST CONTROL ON DISTURBED AREAS	G KAMA	Du	Controlling surface and air movement of dust on construction site, roadways and similar sites.
FI-Co	FLOCCULANTS AND COAGULANTS		FI-Co	Substance formulated to assist in the solids/liquid separation of suspended particles in solution.
Sb	STREAMBANK STABILIZATION (USING PERM VEGETATION)		Sb	The use of readily available native plant materials to maintain and enhance streambanks, or to prevent, or restore and repair small streambank erosion problems.
Ss	SLOPE STABILIZATION		Ss	A protective covering used to prevent erosion and establish temporary or permanent vegetation on steep slopes, shore lines, or channels.
Tac	TACKIFIERS AND BINDERS		Tac	Substance used to anchor straw or hay mulch by causing the organic material to bind together.

							D BY:	
CALL BEFORE YOU DIG!		53		2015			ECKE	
At least 72 hours prior to commencement of the work, the Contractor is responsible for calling the Utilities Protection Center (UPC) at 1-800-282-7411, to request underground utility locate service.	FILE NO.:	2015-003-E	DATE:	MARCH 27,	SCALE:	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	DRAWN BY/CH	CLM/NJH
THIS DRAWING IS AN INSTRUMENT OF SERVICE AND REMAINS THE PROPERTY OF COASTAL ENGINEERING CONSULTANTS, INC. THIS	SH	IEET	NO.	:	7 0			

THE WRITTEN PERMISSION OF COASTAL ENGINEERING CONSULTANTS, INC.

GSWCC CERTIFICATION NO. 0000026 OCC ョョ





). WASHRACKS AND/OR TIRE WASHERS MAY BE REQUIRED DEPENDING ON SCALE AND CIRCUMSTANCE. IF NECESSARY, WASHRACK DESIGN MAY CONSIST OF ANY MATERIAL SUITABLE FOR TRUCK TRAFFIC THAT


RIGHTS-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.


10.MAINTAIN AREA IN A WAY THAT PREVENTS TRACKING AND/OR FLOW OF MUD ONTO PUBLIC


DRAINAGE FROM THE ENTRANCE TO A SEDIMENT CONTROL DEVICE).




















	LEVEL GSW	L II C		DESIGN ION NO	PROI	FESSIONAL 00026209
		Coasial Engineering	Consultants, Inc.		P. O. BOX 1895 BRUNSWICK GFORGIA 31521	(912) 223-0647 PHONE JohnH@cec-ga.com
						DATE
						DESCRIPTION OF REVISION
						REVISION NO.
	2015 CTDEETC DDAINAGE	ZOID SINEEIS, DIVAINAGE		UIILII Y PROJECI	CITY OF WAYCROSS, GEORGIA	DETAILS OF STRUCTURAL BMP'S
CALL BEFORE YOU DIG! At least 72 hours prior to commencement of the work, the Contractor is responsible for calling the Utilities Protection Center (UPC) at 1-800-282-7411, to request underground utility locate service.	FILE NO.:	2015-003-ES4	DATE: MARCH 27, 2015	SCALE:	AS SHOWN	DRAWN BY/CHECKED BY:
THIS DRAWING IS AN INSTRUMENT OF SERVICE AND REMAINS THE PROPERTY OF COASTAL ENGINEERING CONSULTANTS, INC. THIS DRAWING MAY NOT BE REPRODUCED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF COASTAL ENGINEERING CONSULTANTS, NC.	-	EET	NO.:	S-4	_ 4	